

MAR 23 1999

1998

CHEBOYGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Cheboygan

(County)

Located in:

Corner Code #

1. Public Land Survey

T	36N	R	3W	G-2
T		R		
T		R		
T		R		
S		T		
S		T		
S		T		
S		T		

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

S		T		
S		T		
S		T		
S		T		

RECEIVED FOR RECORD 1-8-99  
at 9:07 O'Clock A M

*James Spray*

CLERK/REGISTER  
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		●	3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1855 Harvey Mellon Resurvey Set 1/4 post 8" Cedar N 17° W 18 lks 10" Cedar N 7° E 20 lks	1970 Doyle Civil Engineering Fnd 1" pipe 12" Spruce S 73° E 35.23' 16" Cedar S 23° W 34.65' 16" Cedar N 21° W 11.08'
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 1" pipe  
12" Spruce stump S 73° E 35.23' old wit  
16" Cedar S 23° W 34.5' +/- old wit  
16" Cedar N 21° W 11.08' old wit



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 Placed 5/8" rebar with remonumentation cap inside pipe, and position is accepted as a careful and faithful perpetuation of the original corner.

16" Cedar N 21° W 11.08'	Set tag 41099
10" Cedar N 47° E 19.00'	Set tag 41099
14" W. Birch S 75° E 53.67'	Set tag 41099
36" W. Pine N 85° W 41.16'	Set tag 41099



Signed by *B. K. Fullford*  
Surveyor's Michigan License No. 41099

Date 4/23/98