

MAR 22 1999

SECTION

1998
CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Cheboygan (County)	Located In:	Corner Code #
1. Public Land Survey	T36N R 3W	1-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD 1-8-99
at 9:12 O'Clock A M

Joanne Spray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3	●	2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | | |
|--|--|--|--|
| 1855 Harvey Mellon Resurvey
Set 1/4 post
24" Beech N 21° W 33 lks
7" Beech S 52° W 14 lks | 1905 David Bowen
County Surveyor
1/2 egg shape stone at corner
Cut on top end w/letter B, 5"
deep By 12" and 20" round,
w/1 brick & 4 small stones
around corner No wits given | 1970 Doyle Civil Engineers
Fnd 1" pipe
P. Pole #5440 N 71° 30' W
100.25'
P. Pole N 71° 30' E 54.43'
28" Poplar S 51° E 79.59' | Aug 1975 Mark Ennes #25842
Fnd 1" pipe
P. Pole N 60° E 54.36'
Guy pole S 70° W 99.30'
P. Pole N 70° W 100.18'
Dunn B & C N 7° E 27.7' |
|--|--|--|--|

*See continuation of A on reverse side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Fnd 1/2" Re-rod in Mon box
- 1/2" bar w/cap 12020 N 7° E 33.38'
- 9.0' North of Centerline road
- P. Pole N 73° E 54.34' w/tag 15410
- P. Pole S 20° E 91.42' w/tag 15410
- P. Pole S 09° E 135.94' w/tag 15410
- P. Pole N 65° W 102.50' w/tag 15410



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 Placed remonumentation cap on 1/2" rebar in monument box, and position is accepted as a careful and faithful perpetuation of the original corner.

- P. Pole N 73° E 54.34' w/tag 15410
- P. Pole S 20° E 91.42' w/tag 15410
- P. Pole S 09° E 135.94' w/tag 15410
- P. Pole N 65° W 102.50' w/tag 15410



Signed by *B. K. Fullford*
Surveyor's Michigan License No. 41099

Date 11/23/98

MAR 8 1999

SECTION

A. Continued:

June 1985
Richard Dunn
#12020
Unrecorded survey
drawing only
No wits given

June 1990
Richard Dunn
#12020
Fnd corner
No wits given

July 1995
Norman Quaine
#33984
Fnd 1" pipe
P. Pole N 65° W 102.74'
P. Pole N 73° E 54.34'
P. Pole S 20° E 91.42'
P. Pole S 07° E
136.13'

Jan 1996
Mark Ennes
#25842
Fnd 1" pipe (damaged)
Replaced w/ 1/2" iron rod in
Mon box
P. Pole N 65° W 102.74'
P. Pole N 73° E 54.34'
P. Pole S 20° E 91.42'
P. Pole S 07° E 136.13'

File Wade Truitt

9
2

*CK 5263
C.S09*