

FEB 26 1998

SECTION

CHEBOYGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Cheboygan (County)

Table with columns: Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling, and Miscellaneous Property in Sec.

RECEIVED FOR RECORD 12-18-97 at 11:04 O'Clock A M

Signature of Joanne Spray

CLERK/REGISTER CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Brian K. Fullford, in a field survey on Sept. 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is present at row 3, column J.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. 1905 David Bowen 4" Sq. Cedar Post
1855 Harvey Mellen Old 1/4 plain witness trees by original notes.
Reestablish 1/4 corner
16" Beech S 47° E 35 lks
24" Hemlock N 80° W 22 lks

1993 Norm Quain #33984
1" Pipe @ fence corner fences headed N-S-E
8" Tw. Maple N 25° E 14.09'
16" Beech N 71° W 12.04'
4" Ash S 44° W 10.75'
6" Ash S 07° E 20.92'
**Cites United Design retracement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found 1" pipe and 4 witnesses.

LIBER 011 PAGE 08



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 Placed 5/8" rebar with remonumentation cap inside 1" pipe, and is accepted as a careful and faithful perpetuation of the original corner.

8" Tw. Maple N 25° E 14.09' W/ Tag 15410
16" Beech S 7° E 12.04' W/ Tag 15410
6" Ash S 44° W 10.49' W/ Tag 15410
8" Ash S 21° W 20.92' W/ Tag 15410
Fence line heads N-S-E



Signed by [Signature] Surveyor's Michigan License No. 41099

Date 11/21/97