

MAR 22 1999

1998

CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
Cheboygan

_____	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 36N R 3W	<u>K-1</u> ✓
	T 37N R 3W	K-13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD 1-8-99
at 9:14 O'Clock A M

Joanne Spray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	19		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1840 John Mullett
Original Survey
Set post
10" Hemlock N 65° E 25 lks
24" Hemlock N 45° W 43 lks

1855 Harvey Mellon
Resurvey
Fnd old post 6 lks West
16" Beech S 16° E 12 lks
20" Y. Birch S 55 1/2° W 36 lks

1905 David Bowen
County Surveyor Fnd Cedar
post 4 1/2" Sq.
Y Birch stump S 55 1/2° W 36 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 5/8" gun barrel
Old fence post S 58° E 35.02' w/ tag 15401
14" Tw. Red Pine S 35° W 83.86' w/ tag 15401
12" W. Pine S 62° W 63.69' w/ tag 16041
12" W. Pine S 68° W 65.79' w/ tag 15401
Fence post N 20° W 95.76' w/ tag 16041
6' East of road intersection

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Placed 5/8" rebar with remonumentation cap next to gun barrel, and position is accepted as a careful and faithful perpetuation of the original corner.

Old fence post S 58° E 35.02' w/ tag 15401
14" Tw. Red Pine S 35° W 83.86' w/ tag 15401
12" W. Pine S 62° W 63.69' w/ tag 16041
12" W. Pine S 68° W 65.79' w/ tag 15401
Fence post N 20° W 95.76' w/ tag 16041
6' East of road intersection

NOTE: THIS CORNER IS ALSO DESIGNATED AS CODE K-13 IN T37N-R3W.

Signed by *B. K. Fullford*
Surveyor's Michigan License No. 41099

Date 11/23/98

