

MAR 2 1999

1998

SECTION

CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Cheboygan

(County)

Located In:

Corner Code #

1. Public Land Survey

T	36N	R	3W	K-2
T		R		
T		R		
T		R		
T		R		

2. Property Controlling
in Section

S		T		R	
S		T		R	
S		T		R	
S		T		R	

3. Miscellaneous
Property in Sec.

RECEIVED FOR RECORD 1-8-99
at 9:15 O'Clock A.M.

Joanne Spray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2	●	1	
3												
4	7		8		9		10		11		12	
5												
6	19		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1855 Harvey Mellon
Resurvey
Set 1/4 post
24" Hemlock S 54 1/2° E 52 lks
20" Beech N 62 1/2° W 60 lks

1905 David Bowen
County Surveyor
Fnd points of old stake
Set Cedar 2 X 3 w/wagon
scane on point of post filled
hole w/stone
No other wits given

Oct 1968 Orlando Doyle #7319
Fnd "T" Bar
P. Pole N 51° 30' E 44.15'
Fence cor. N 47° 30' W 44.75'
30" Poplar S 51° W 140.69'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd "T" Bar
10' North of road intersection
P. Pole N 51° 30' E 44.04' w/ old tag
48" Poplar S 51° W 140.48' w/ old tag

James H. Kranger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Placed 5/8" rebar with remonumentation cap over t-bar, and position is accepted as a careful and faithful perpetuation of the original corner.

10' North of road intersection	
P. Pole N 51° 30' E 44.04'	Set tag 41099
48" Poplar S 51° W 140.48'	Set tag 41099
10" Poplar S 39° E 64.66	Set tag 41099
8" Aspen N 21° W 73.48'	Set tag 41099

Signed by *B. K. Fullford*
Surveyor's Michigan License No. 41099

Date 11/23/98

