

**SURVEY & REMONUMENTATION**

FEB 26 1998

SECTION \_\_\_\_\_

**CHEBOYGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Cheboygan  
(County)

Located In: T36NR 3W Corner Code # K-3  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD 12-18-97  
 at 11:00 Clock A M

*Joanne Spray*

CLERK/REGISTER  
 CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Brian K. Fullford, in a field survey on Sept. 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. 1905&1908 David Bowen 1960 Dean DeLaMater  
 1855 Harvey Mellen Found old stake, set 1/2" rod in concrete monument  
 Reestablished old corner 10 gallons stone with 10" Maple N 50° E 60.52'  
 16" Beech S 43° E 44 lks Cedar post 16" Apple S 49° W 53.75'  
 8" Beech N 44° W 17 lks 6" Beech S 81° E 41.19'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1" pipe and 4 witnesses.

A.) Continued:	1989 James Granger #16041	1993 Norm Quaine #33984
1968 Orlando Doyle #7319	1" Pipe	1" Pipe 6' West of N-S gravel Rd
1/2" iron bar	10" Maple N 67° E 45.03'	10" Oak S 75° W 23.45'
15" Maple S 7° E 170.47'	8" R. Oak N 75° W 23.38'	8" S. Pine N 30° W 50.30'
15" Maple S 18° 30' W 116.02'	8" R. Pine N 41° W 50.30'	20" Aspen N 41° E 54.24'
8" Maple N 67° E 45.05'	10" Beech S 75° E 41.15'	10" Aspen S 79° E 24.52'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 K-3 Replaced 1" pipe (could not drive pipe down) with 5/8" rebar with remonumentation cap 6" below surface and is accepted as a careful and faithful perpetuation of the original corner.

24" Aspen N 34° E 54.22'	W/ Tag 15410
12" Aspen S 84° E 24.48'	W/ Tag 15410
12" Oak N 77° W 23.46'	W/ Tag 15410
10" S. Pine N 44° W 50.30'	W/ Tag 15410



Signed by Brian K. Fullford  
 Surveyor's Michigan License No. 41099

Date 11/21/97