

FEB 26 1998

**SECTION CHEBOYGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Cheboygan  
 (County)

Located In:	Corner Code #
1. Public Land Survey <u>T36N R 3W</u>	<u>K-7</u>
T <u>    </u> R <u>    </u>	<u>    </u>
T <u>    </u> R <u>    </u>	<u>    </u>
T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling In Section S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec. S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

RECEIVED FOR RECORD 10-18-97  
 at 11:10 O'Clock A M  
*Joanne Spray*  
 CLERK/REGISTER  
 CHEBOYGAN COUNTY, MICHIGAN  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Brian K. Fullford, in a field survey on Aug. 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. 1974 & 1979 Richard Bidstrup #11360  
 1855 Harvey Mellen 12" Oak S 24° W 30.7'  
 14" Sugar N 61° E 6 lks 3" Pine S 58° E 31.4'  
 16" Beech S 56° E 33 lks TW. Apple S 66° W 63.7'  
 Liber 355, Page 394,  
 Liber 401, Page 674,  
 Liber 374, Page 652



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 3/4" pipe with 3 witnesses (1 dying).

LIBER **011** PAGE **14**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 K-7 Replaced 3/4" pipe with 5/8" rebar with remonumentation cap and is accepted as a careful and faithful perpetuation of the original corner.

- 16" W. Pine S 65° E 32.42' Set Tag 41099
- 18" W. Pine S 47° E 34.07' Set Tag 41099
- 36" Oak South 79.15' Set Tag 41099
- 21" Oak S 22° W 30.57' Set Tag 41099



Signed by Brian K. Fullford  
 Surveyor's Michigan License No. 41099

Date 11/21/97