

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

**CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Cheboygan
(County)

Located In: T36N R 3W Corner Code # K-8
 T ___ R ___
 T ___ R ___
 T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Brian K. Fullford, in a field survey on Sept 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. Orlando Doyle #7319
 1855 Harvey Mellen Set Conc. Monument
 Reestablish old 1/4 cor. 10" Poplar N 40° W 35.60'
 8" Beech S 25° W 9 lks 20" T-Oak S 69° E 35.30'
 8" Beech N 37° E 18 lks North fence 19.00'
 Corner set 6' East of N-S fence

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found concrete monument, fence remnants 19' North and 2 Maple trees scarred.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-8 Set remonumentation cap on monument and is accepted as a careful and faithful perpetuation of the original corner.

10" Oak N 15° E 25.30'
 18" Maple S 64° E 56.40'
 15" Maple S 16° W 48.78'
 18" Red Pine N 51° W 58.87'

O/H Electric lines 2.5' North and 126' East.

Signed by Brian K. Fullford
 Surveyor's Michigan License No. 41099

Date 11/21/97

RECEIVED FOR RECORD 12-18-97
 at 11:11 O'Clock A M

Joanne Spray

CLERK/REGISTER
 CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



LIBER 011 PAGE 15

