

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

**CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Cheboygan
(County)

Located In:

Corner Code #

1. Public Land Survey

T36N R 3W K-9
T ___ R ___
T ___ R ___
T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian K. Fullford, in a field survey on Sept. 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	1927 Plat of Happy Heights	1972 Orlando Doyle #7319
1855 Harvey Mellen	David Bowen	Concrete Mon. With pipe
Reestablish old corner	Concrete Monument	8" Elm (1 of 2) S 74° 30' E 17.53'
12" Y. Pine 55° W 11 lks	12" Y. Pine S 55° W 11 lks	5" Oak S 18° W 12.63'
22" W. Pine N 48° W 12 lks	22" W. Pine N 48° W 12 lks	8" Oak N 21° W 20.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe in concrete, 3 witnesses, and original stump.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

RECEIVED FOR RECORD 12-18-97
at 11:12 O'Clock A M

Joanne Spray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number



LIBER **011** PAGE **16**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Placed 5/8" rebar with remonumentation cap inside 1" pipe, and is accepted as a careful and faithful perpetuation of the original corner.

4" Sq. concrete monument N 50° E 46.11'
8" Twin Oak S 74° E 17.70'
7" Oak S 23° W 12.49'
12" Twin Oak N 20° W 19.96'

Set Tag 41099
Set Tag 41099
Set Tag 41099



Signed by Brian K. Fullford
Surveyor's Michigan License No. 41099

Date 11/21/97