

**SURVEY & REMONUMENTATION**

FEB 26 1998

SECTION

**CHEBOYGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Cheboygan  
(County)

Located In:	Corner Code #
T36NR 3W	L-5
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD 12-18-97  
at 11:16 O'Clock A.M.

*James H. Granger*

CLERK/REGISTER  
CHEBOYGAN COUNTY, MICHIGAN  
Register of Deeds Stamp & File Number

I, Brian K. Fullford, in a field survey on Nov. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- |                      |                         |                             |
|----------------------|-------------------------|-----------------------------|
| G.L.O.               | 1960 Dean DeLaMater     | 1989 James Granger #16041   |
| 1855 Harvey Mellen   | 3/4" iron               | 1/2" rod                    |
| Set 1/4 Section post | SW Cor store N 42° W    | 4" Sq. Con. R-O-W marker    |
| 10" Beech N 27° W    | 66.50'                  | N 33° E 67.83'              |
| 6 lks                | 12" Oak S 37° W 113.58' | Stop sign S 3° E 86.20'     |
| 16" Sugar S 72° E    | 5" Oak S 52° W 94.53'   | 12" Oak S 54° W 100.58'     |
| 13 lks               |                         | SW cor store N 48° W 77.75' |

- 1992 Richard C. Dunn  
#12020  
1/2" iron  
R/W Marker NE 67.80'  
Util Pole NNW 78.83'  
SW Cor Bldg NW 77.80'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" iron rod and 4 witnesses per 1989 L.C.R.C..



LIBER 011 PAGE 20

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 Placed 5/8" rebar with remonumentation cap over top of 1/2" rod in monument box and is accepted as a careful and faithful perpetuation of the original corner.

R/W Marker N 30° E 67.80'  
Sign post S 10° E 86.30'  
SW Cor Bldg. N 53° W 77.80'  
P. Pole N 22° W 79.07'

Set Tag 41099

Signed by *B. K. Fullford*  
Surveyor's Michigan License No. 41099

Date 11/21/97

