

SURVEY & REMONUMENTATION

FEB 26 1998

**CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Cheboygan

(County)

Located In:

Corner Code #

1. Public Land Survey

T36N R 3W Corner Code # L-11
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Brian K. Fullford, in a field survey on Sept 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	1947 Orlando	1961 Dean DeLaMater
1855 Harvey Mellen	Doyle #7319	#5778
Set 1/4 Section post	Set Conc. Mon.	Concrete Monument
10" Y Pine N 56° E 11 lks	22" Oak NW 32.2'	30" Maple N 30° W 33.16'
16" Y. Pine N 73° W 20 lks	22'	24" Oak S 5° W 42.53'
	12" Tw. Oak SW 42.0'	12" Oak N 60° E 48.45'

1997 Michael Trowbridge #27463 Found Concrete Monument Notes Liber 13, Pg. 38, CCR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument, 3 witnesses, and rotted Maple and Oak stumps.



LIBER **011** PAGE **23**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Placed remonumentation cap on monument, and is accepted as a careful and faithful perpetuation of the original corner.

P.Pole N 38° E 26.88'	W/Tag #41099
6" White Pine S 60° E 18.28'	W/Cap # 27463
6" White Pine S 61° E 37.62'	W/Cap #27463
6" Oak S 78° W 46.55'	W/ Tag #41099
5' South of 2-track centerline	
Old fence 22' West	



Signed by Brian K. Fullford
 Surveyor's Michigan License No. 41099

Date 11/21/97

Register of Deeds Stamp & File Number

RECEIVED FOR RECORD 12-18-97
 at 11:19 O'Clock AM

Joanne Spray

CLERK/REGISTER
 CHEBOYGAN COUNTY, MICHIGAN

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													