

MAR 28 1999

1998

CHEBOYGAN COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in  
 Cheboygan

Located in: Corner Code #

(County)

1. Public Land Survey	T <u>36</u> N R <u>3</u> W	<u>11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD 1-8-99  
 at 9:03 O'Clock A M

*Joanne Spray*

CLERK/REGISTER  
 CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1855 Harvey Mellon Resurvey  
 6" W. Birch on meander corner  
 10" Cedar N 43° W 15 lks  
 Cedar swamp to lake  
 Original G.L.O. distance 4.68 chains (308.9 feet)  
 1970 Doyle Civil Engineers  
 Unrecorded Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Fnd Conc Mon with U of M cap RLS #7319  
 79.06 Feet North of original G.L.O. Meander corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 E3-E4 Use existing concrete monument with U of M cap & RLS #7319, and position is accepted as a careful and faithful perpetuation of the original corner.

- 10" Cedar N 36° E 4.46' Set tag 41099
- 6" Ash S 72° E 16.90' Set tag 41099
- 5" Tw. Birch N 75° W 9.18' Set tag 41099
- 4" Tw. Maple N 14° W 10.00' Set tag 41099
- High water mark N 72° E 34.5' +/-
- High water mark South 40' +/-



Signed by *B. K. Fullford*  
 Surveyor's Michigan License No. 41099

Date 11/23/98