

**SURVEY & REMONUMENTATION**

1993

**COMMISSION**

**CHEBOYGAN COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

CHEBOYGAN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>37N</u> R <u>1E</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECEIVED  
FOR RECORD**

**93 DEC 22 AM 10:34**

*Joanna Garcia*

Register of Deeds, Clerk/Registrar & File Number  
CHEBOYGAN COUNTY, MICHIGAN

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald R. Bischer, in a field survey on September 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- A-12  
 1840 Original Survey (June 12)  
 John Hodgson set Wood Post  
 10" Balsam S30°E 12 links  
 8" Balsam N29°W 9 links  
 1854 Resurvey - Geo. H. Cannon  
 Found and used post set by Hodgson  
 1951 - Joseph Doyle  
 Found 1" Iron
- Fence Post SE 42.71'  
 Fence Post NE 48.93'  
 1974 - Orlando Doyle set 3/4" pipe from  
 Joseph Doyle witnesses  
 Fence Post S48°30'E 42.71'  
 Fence Post N62°00'E 48.93'  
 Fence Post N72°30'W 35.34'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- A-12  
 Found 3/4" pipe and 3 Doyle witnesses from above  
 Found RxR Spike 3.82' N43°E from 3/4" pipe  
 Found Plow Point 10.03' N03°E from 3/4" pipe  
 Found 1/2" x 1" Iron 4.72' N42°W from 3/4" pipe
- Replaced Doyle 3/4" Pipe with Cheboygan County  
 Remonumentation Monument

*Marvin A. Ross*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- A-12  
 Cheboygan County Remonumentation Monument  
 N76°W 35.20' Fence Corner  
 N58°W 44.11' 3" Apple Tree \*  
 N47°E 55.17' Fence Post \*  
 S54°E 42.71' Fence Corner

LIBER **010** PAGE **22**

\*Set witness tags #22428

Signed by Ronald R. Bischer Date 12-03-93  
 Surveyor's Michigan License No. 22428