

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 1 E.
T. 38 N.R. 1 E.


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections: 5 - 6 - 31 - 32

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED October 10, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

6" R. Pine N 83 W 11.5'

5" R. Pine N 80 E 18.4

AND

8" R. Pine S 13 E 34.9

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between corner 1/2 mile east and one mile west while making a survey in this area. Unable to positively identify U. S. BPs, but this point conforms very well with the U. S. notes, to swamp edges in all directions, and appears to be properly located.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE December 12, 1963
REGISTERED LAND SURVEYOR # 10,068