

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 1 E.
T. 38 N.R. 1 E.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 5 - 32

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED October 10, 1963

WITNESSES TO CORNER.....



5" Maple N 68 W 18.8'

5" Maple N 5 E 32.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this area. Found squared cedar stake at corner as established in previous survey. Stumps of U. S. BTs in place with possible evidence of face on NW stump. Conforms well with good corner east, and fits very good by proportion.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE December 11, 1963
REGISTERED LAND SURVEYOR #10,068