

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 37 N.R. 1 E.


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 25 - 26 - 35 - 36

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 13, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" W. Birch N 3 W 11.6'

9" W. Birch S 62 E 47.9

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was found while making a survey in this area. Found 1 1/2" pipe at corner as established in previous survey. Can find no original evidence but corner checks okay for centerline of road south, and fair for distance and line east to good corner; and was considered best available evidence.

**SURVEYOR'S SEAL**

SIGNED Kenneth J. Ostling DATE December 17, 1963  
REGISTERED LAND SURVEYOR  
#10,068