

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 1 E


Cheboygan COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 22-23-26-27

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 12-19-63

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" wh. Pine S 17 W 84.9

3" r. Pine N 89 W 42.3

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey in this area. Set corner on line over good $\frac{1}{4}$ and Section corner West, at a distance there from which makes the $\frac{1}{2}$ miles of 22-27 of equal measurement. Corner falls in open marsh and cannot identify U. S. evidence. Checks swamp edges okay, however, and checks okay with good $\frac{1}{4}$ corner between 22-27.

SURVEYOR'S SEAL

SIGNED *Fennel Osting* DATE January 2, 1964
REGISTERED LAND SURVEYOR #10,068