

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N. R. 1 E


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 Corner common to Sections 34-35

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 12/19/63

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" Cedar S 60 W 25.6

10" Birch N 10 W 35.2

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey in this area. Set corner at record U.S. measure north of recovered meander corner (3.85 chain) on line over good corners South. It was felt that the meander corner presented a satisfactory witness to the $\frac{1}{4}$ corner and this method of restoration would place it very nearly in its original position. Nothing left for U.S.L.T.s on any previous corner.

SURVEYOR'S SEAL

SIGNED *Kenneth H. Osting* DATE December 30, 1963
REGISTERED LAND SURVEYOR 10,068