

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N. R. 1 E.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 3 - 10

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 12, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

24" W. Pine stp N 57 E 12.6'

7" Balsam S 40 E 19.1

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey in this area. Set corner from probable U.S. BT stumps which are both down and burned, but possible evidence of upper face on NW. Falls within 15 links of proportionate measurement and was considered very likely an original restoration.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Pilling* DATE December 17, 1963
REGISTERED LAND SURVEYOR #10,068