

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 37 N. R. 1 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 29 - 30 - 31 - 32

CORNER MONUMENT Drove 1" iron bar in road

DATE MONUMENT PLACED AND WITNESSED December 10, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

6" Cedar N 76 E 31.2'

8" Tamarack S 52 W 15.2

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was set by proportionate measurement between corners 1/2 mile west, one mile east, 1/2 mile south and two miles north. Unable to identify anything for U. S. evidence. Corner falls in E - W road (Badger Truck Trail). Found old stake about 60 links SW but does not appear to have been set as corner and does not conform to pattern of survey for this area.

**SURVEYOR'S SEAL**

SIGNED *Kenneth J. Ostling* DATE December 17, 1963  
REGISTERED LAND SURVEYOR #10,068