

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD


T. 37 N.R. 1 W.  
T. 38 N.R. 1 W.  
Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 2 - 35

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED October 30, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

9" R. Pine N 56 E 54.2'

20" R. Pine S 26 E 67.4'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was established by proportionate measurement, midpoint on line between section corners, while making a survey in this township. No evidence of a previous corner.

SURVEYOR'S SEAL

SIGNED Kenneth Ostling DATE October 30, 1963  
REGISTERED LAND SURVEYOR