

**SURVEY & REMONUMENTATION**

MAR 22 1999

1998

**CHEBOYGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

Cheboygan

(County)

Located In:

Corner Code #

1. Public Land Survey

T36N R 3W  
T36N R 4W  
T37N R 3W  
T37N R 3W

A-1  
M-1  
A-13 ✓  
M-13

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD 1-8-99  
at 8:55 O'Clock A M

*James H. Sharger*

CLERK/REGISTER  
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

NOTE: THIS CORNER IS ALSO DESIGNATED AS CODE M-1, T36N-R4W, CODE A-13, T37N-R3W, & CODE M-13, T37N-R4W.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
1840 Wm. Burt  
Set Post  
12" Hemlock N 13° E 17 lks  
12" Hemlock S 57 1/2° W 25 lks

1893 Sidney Main,  
County Surveyor  
Fnd stumps of Gov't bearing trees;  
Set N.B.T.'s  
8" Birch N 5° 45' E 28 3/4 lks  
6" Birch S 6° E 80 lks  
4' Cedar post S 0° E, 50 lks  
4' Cedar post N 0° E 50 lks

Sept 1976  
Herbert Fluharty #18223  
Fnd spike in Black-Top  
6' +/- East of Fence to North  
off Fence to South  
Road sign N 30° W 22.33'  
6" Poplar S 27° W 50.56'  
10" Tw. Maple S 14° E 60.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 5/8" re-rod in monument box 1' North of centerline road  
Fnd Fence to South  
Fnd 8" Poplar S 27° W 50.61 w/nail & blaze  
Fnd 14" Tw. Maple S 14° E 60.21 w/nail & blaze  
Fnd 10" Cedar N 33° W 37.22 w/tag 15401  
Fnd road sign N 30° W 22.85



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Placed remonumentation cap on 5/8" rebar in monument box, and position is accepted as a careful and faithful perpetuation of the original corner.

1' North of road centerline  
Fence to South  
8" Poplar S 27° W 50.61' w/nail & blaze  
14" Tw. Maple S 14° E 60.21' w/nail & blaze  
10" Cedar N 33° W 37.22' w/tag 15401  
Road sign N 30° W 22.85'

Signed by B. K. Fullford  
Surveyor's Michigan License No. 41099

Date 11/23/98

