

SURVEY & REMONUMENTATION

MAR 2 1999

1998

CHEBOYGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Cheboygan

(County)

Located In:

Corner Code #

1. Public Land Survey

T 36N R 3W

T 37N R 3W

T R

T R

T R

T R

T R

T R

D-1

D-13

2. Property Controlling in Section

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840 John Mullett
Original Survey
Set 1/4 post
7" Maple N 25° W 47 lks
6" Beech N 62° E 38 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 5/8" pipe under Asphalt Rd.
7' North of Centerline Road
28' +/- West of Centerline Two-track to North
42' +/- West of Centerline Two-track to South
P. Pole #1583 N 18° E 52.54' w/ old tag no id
13" R. Pine S 9° E 51.07' w/ old tag no id
12" R. Pine S 22° W 54.25' w/ old tag no id

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Replaced 5/8" pipe with 5/8" rebar with remonumentation cap in monument box, and position is accepted as a careful and faithful perpetuation of the original corner.

P. Pole #1583 N 18° E 52.54' w/ tag
15" R. Pine S 50° E 76.99' Set tag 41099
13" R. Pine S 9° E 51.07' w/ tag
12" R. Pine S 22° W 54.25' w/ tag

NOTE: THIS CORNER IS ALSO DESIGNATED CODE D-13 IN T37N-R3W.

Signed by B. K. Fullford
Surveyor's Michigan License No. 41099

Date 11/23/98

RECEIVED FOR RECORD 1-8-99
at 8:59 O'Clock A M

Joanne Spray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

