

SURVEY & REMONUMENTATION

MAR 22 1999

1998

CHEBOYGAN COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Cheboygan
(County)

Located in:	Corner Code #
T36N R 3W	J-1
T37N R 3W	J-13 ✓
T R	
T R	
S T R	
S T R	
S T R	
S T R	

RECEIVED FOR RECORD 1-8-99
at 9:13 O'Clock A M

Joanne Gray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1										●			
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1840 John Mullett Original Survey Set 1/4 post 6" Hemlock N 45° W 16 lks 10" Beech N 45° E 20 lks
- 1905 David Bowen County Surveyor Fnd Cedar post 2 1/2" Sq. w/gun barrel driven along side No wits given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Fnd 3/4" pipe in center of small stone pile
- 10" Maple S 15° E 21.65' w/ old blaze
- 12" Maple S 38° W 27.69' w/ old blaze
- 12" Poplar S 81° W 34.22' w/ old blaze
- 18" Poplar S 79° E 5.60' w/old blaze located in wooded area at SW corner of farm field 100' +/- into woods

James H. Branger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-1 Placed 5/8" rebar with remonumentation cap inside pipe, and position is accepted as a careful and faithful perpetuation of the original corner.
- 12" Maple N 18° E 48.65' Set tag 41099
- 10" Maple S 15° E 21.65' Set tag 41099
- 12" Maple S 38° W 27.69' Set tag 41099
- 12" Poplar S 81° W 34.22' Set tag 41099

NOTE: THIS CORNER IS ALSO DESIGNATED AS CODE J-13 IN T37N-R3W.

Signed by B. K. Fullford
Surveyor's Michigan License No. 41099

Date 11/23/98

