

**SURVEY & REMONUMENTATION**

MAR 22 1999

1998  
CHEBOYGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION  
Cheboygan

(County)	Located In:	Corner Code #
1. Public Land Survey	T <sup>36N</sup> R <sup>3W</sup>	K-1
	T <sup>37N</sup> R <sup>3W</sup>	K-13
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD 1-8-99  
at 9:14 O'Clock A.M.

*James Gray*

CLERK/REGISTER  
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Brian K. Fullford, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4		3		2		1		
3													
4	7	8			9		10		11		12		
5													
6	18	17			16		15		14		13		
7													
8	19	20			21		22		23		24		
9													
10	30	29			28		27		26		25		
11													
12	31	32			33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- |  |  |  |
|--|--|--|
| 1840 John Mullett<br>Original Survey<br>Set post<br>10" Hemlock N 65° E 25 lks<br>24" Hemlock N 45° W 43 lks | 1855 Harvey Mellon<br>Resurvey<br>Fnd old post 6 lks West<br>16" Beech S 16° E 12 lks<br>20" Y. Birch S 55 1/2° W 36 lks | 1905 David Bowen<br>County Surveyor Fnd Cedar<br>post 4 1/2" Sq.<br>Y Birch stump S 55 1/2° W 36 lks |
|--|--|--|

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Fnd 5/8" gun barrel
  - Old fence post S 58° E 35.02' w/ tag 15401
  - 14" Tw. Red Pine S 35° W 83.86' w/ tag 15401
  - 12" W. Pine S 62° W 63.69' w/ tag 16041
  - 12" W. Pine S 68° W 65.79' w/ tag 15401
  - Fence post N 20° W 95.76' w/ tag 16041
  - 6' East of road intersection

*James H. Sawyer*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-1 Placed 5/8" rebar with remonumentation cap next to gun barrel, and position is accepted as a careful and faithful perpetuation of the original corner.

Old fence post S 58° E 35.02' w/ tag 15401  
14" Tw. Red Pine S 35° W 83.86' w/ tag 15401  
12" W. Pine S 62° W 63.69' w/ tag 16041  
12" W. Pine S 68° W 65.79' w/ tag 15401  
Fence post N 20° W 95.76' w/ tag 16041  
6' East of road intersection

NOTE: THIS CORNER IS ALSO DESIGNATED AS CODE K-13 IN T37N-R3W.

Signed by *B. K. Fullford*  
Surveyor's Michigan License No. 41099

Date 11/23/98

