

CHEBOYGAN COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHEBOYGAN _____ Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 37NR 2W _____ C-5
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD 12-18-97
at 11:23 o'Clock A M

James Gray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

JAMES H. GRANGER, in a field survey on JULY 15, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1-5 1855 Original Survey Set wood post 20" W. Pine N77°E 1.77 lks
Harvey Mellen
- 1979 Survey 1/2" pipe
Orlando Doyle #7319

SURVEY &
REMONUMENTATION

FEB 26 1998

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1-5 Found 1/2" pipe and 4 witnesses from 1979 survey. Replaced with 5/8" rebar and remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1-5 5/8" rebar and Remonumentation Cap
- 14" Tamarack S23°W 42.57' Fd nail and washer
- 16" W. Pine N28°W 40.46' Fd nail and washer
- 6" Tamarack N80°E 16.38' Fd nail and washer
- 4" Spruce N35°E 7.03' Fd nail and washer

LIBER 011 PAGE 27

Signed by James H. Granger
License No. 16041

Date Nov. 17, 1997 Surveyor's Michigan

