

SURVEY & REMONUMENTATION

CHEBOYGAN COUNTY REMONUMENTATION

RECEIVED FOR RECORD

MAY 03 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 22 AM 9:59

For corners in **CHEBOYGAN**
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>38N</u> R <u>1W</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

James H. Granger
CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James H. Granger, in a field survey on August 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840 Original Survey Set Wood Post, 12" Cedar N88°W 37 lks, 8" Spruce N45°E 15 lks
- John Mullett
- 1894 John McDonald Plat Monument
- 1894 G.D.V. Rollo Plat Monument
- 1964 Ken Larsen #10695 Fd iron
- 1979 Orlando Doyle #7319 Fd metal monument @ corner
- 1986 Orlando Doyle #7319 Fd metal monument @ corner
- 1992 Clifford Lindgren #14098 Set Pk Nail (MDOT)
- 1994 James Granger #16041 Fd Pk Nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd Pk nail. Fd witnesses. Reset 5/8" rebar w/aluminum cap in Monument Box.

Marvin A. Rose

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5/8" rebar w/aluminum cap in Monument Box
- PP S74°W 54.68'
- PP S36°E 34.92'
- PP N49°E 29.34'
- PP N41°W 32.42'

LIBER **010** PAGE **57**

Signed by James H. Granger Date 11-18-94
Surveyor's Michigan License No. 16041