

SURVEY & REMONUMENTATION
CHEBOYGAN COUNTY REMONUMENTATION

RECEIVED FOR RECORD

101 MAY 03 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 22 AM 9:44

For corners in
Cheboygan
 (County)

COMMISSION

Joanna Spray
 CLERK/REGISTER
 CHEBOYGAN COUNTY, MICHIGAN

	Located In:	Corner Code #:
1. Public Land Survey	T <u>38N</u> R <u>1W</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, James H. Granger, in a field survey on August 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1855 Original Survey Set wood post, 10" Cedar S 8°E 13 lks, 12" Cedar N 31°W 13 lks
- Harvey Mellen
- 1874 John McDonald Plat Monument
- 1981 Orlando Doyle #7319 Fd 3/4" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd 3/4" pipe. Fd 3 witnesses. Reset 5/8" rebar with aluminum cap in Monument Box. Placed 4th witness.

Maurice A. Ross

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5/8" rebar w/ aluminum cap in Monument Box
- 20" Chestnut S 84°E 35.62'
- 16" Maple N 56°E 31.29'
- NE cor Bldg S 62°W 66.95'
- PP N 13°W 75.62'

LIBER **010** PAGE **50**

signed by James H. Granger Date 11-18-94
 Surveyor's Michigan License No. 16041