

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
CHEBOYGAN

	Located In:	Corner Code #
(County)		
1. Public Land Survey	T. <u>38N</u> R. <u>3W</u>	<u>M-8</u>
	T. <u>    </u> R. <u>    </u>	<u>    </u>
	T. <u>38</u> R. <u>3W</u>	<u>A-8</u>
	T. <u>    </u> R. <u>    </u>	<u>    </u>
2. Property Controlling in Section	S. <u>    </u> T. <u>    </u> R. <u>    </u>	<u>    </u>
	S. <u>    </u> T. <u>    </u> R. <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S. <u>    </u> T. <u>    </u> R. <u>    </u>	<u>    </u>
	S. <u>    </u> T. <u>    </u> R. <u>    </u>	<u>    </u>

RECEIVED  
FOR RECORD  
96 OCT 30 PM 12:17  
*James H. Granger*  
CLERK/REGISTER  
CHEBOYGAN COUNTY, MICHIGAN  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, JAMES H. GRANGER, in a field survey on SEPTEMBER 24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840 Original Survey                      Set wood post 12" Cedar N19°W    19 lks  
John Mullett                                      10" Cedar S19°E    21 lks

1964 DNR - LCRC                              Set 1" pipe w/4" brass cap  
Ken Larsen # 10695

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found DNR monument brass cap and two witnesses.

*Martin O. Ross*  
Cheboygan County  
OCT 30 1996  
Re-Monumentation

LIBER 010 PAGE 175

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
also corner A-8, T38N, R2W  
DNR monument with brass Cap

JAMES H. GRANGER  
PROF. SURVEYOR  
MICHIGAN  
13041

10" Cedar	N27°W	25.49'	Set nail w/tag in scribed tree
16" Poplar	S68°W	4.41'	Set nail w/tag
14" Cedar	S78°E	22.14'	Set nail w/tag in scribed tree
6" Cedar	S24°E	12.80'	Set nail w/tag

Signed by James H. Granger  
Surveyor's Michigan License No. 16041

Date 10-10-96