

**SURVEY & REMONUMENTATION**  
**CHEBOYGAN COUNTY REMONUMENTATION CORNER**

FEB 26 1998

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>CHEBOYGAN</u> SECTION	Located In:	Corner Code #
(County)		
1. Public Land Survey	<u>38N 2W</u> T <u>37NR</u> 2W	<u>C-13</u> <u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD 12-18-97  
 at 11:21 O'Clock A M  
*Joanne Gray*  
 CLERK/REGISTER  
 CHEBOYGAN COUNTY, MICHIGAN  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, JAMES H. GRANGER, in a field survey on JULY 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-1 1840 Original Survey                      36" Pine Corner  
     John Mullett
- 1972 Survey                                      Metal Monument  
     Orlando Doyle #7319
- 1977 LCRC                                        Concrete Monument  
     Orlando Doyle #7319

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-1 Found concrete monument and 2 existing witnesses grown over. Set remonumentation cap on concrete monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1 Concrete Monument with Remonumentation Cap
- 16" Poplar N19°W 86.42' Set tag #16041
- PP N19°E 115.65' Set tag #16041
- 24" Maple S62°E 18.41' Set tag #16041
- PP S57°W 48.08' Fd tag #41099

LIBER **011** PAGE **25**

Signed by James H. Granger Date Nov. 17, 1997 Surveyor's Michigan License No. 16041

