CHEBOYGAN COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	(2-18-9-
CHEBOYGAN Located In: Corner Code #	RECEIVED FOR RECORD O'Clock AM
1. Public Land Survey T 37NR 2W T R T R	JosenneSpray
T R	CLERK/REGISTER CHEBOYGAN COUNTY,MICHIGAN
Property in Sec. S TR	Register of Deeds Stamp & File Number
4. Lot No, Recorded Plat 5. Private Claims	A B C D E F G H I J K L M
	2 6 5 4 3 2 1
I, <u>JAMES H. GRANGER</u> , in a field survey on <u>JULY 15</u> , 19 <u>97</u> do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:	4 7 8 9 10 11 12 5 6 19 17 16 15 14 13 7 8 19 20 21 22 23 24
NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.	9 10 30 -29 28 -27 -26 -25 11
A. Description of original monument and accessories and/or subsequent restoration:	12 31 32 33 34 35 36
F-1 1840 Original Survey Set wood post 10" Cedar N38°W 23 lks John Mullett 8" Cedar N56°E 12 lks	ovan C
1955 Survey 3/4" pipe Orlando Doyle #7319	Chepoygan County
SURVEY & REMONUMENTATION	SEP 2 5 1997
FEB 2 6 1998	James H Granger
SECTION	
B. Description of corner evidence found and/or method applied in restoring or reestablishing corn	eer:
F-1 Found 3/4" pipe at corner position. Replaced with 5/8" rebar and remonumentation cap.	
C. Description of monument for corner and accessories established to perpetuate locating the pos	sition of the corner:
F-1 5/8" rebar and Remonumentation Cap 4" Cedar S 4°E 18.86' Set tag #16041 14" Poplar S37°W 24.25' Set tag #16041 4" Poplar N79°W 38.50' Set tag #16041 4" Maple N37°E 17.04' Set tag #16041	,
Signed by James H Llarge Date No	V 17, 1997 Surveyor's Michigan
License No. 16041	Surveyor & witchigan
PORM APPROVED BY MICHIGAN STATE BO	
JAMES H. GRANGER PROFESSIONAL SUSVEYOR FORM APPROVED BY MICHIGAN STATE BO. LIBER LIBER	ARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED 14,1976 REVISED JAN., 1983 REVISED OCT., 1996
PROFESSIONAL SURVEYOR 5	11 page 33

No. 16041 LIBER 011 PAGE 33