

SURVEY & REMONUMENTATION

CHEBOYGAN COUNTY REMONUMENTATION

RECEIVED FOR RECORD

MAY 03 1995

LAND CORNER RECORDATION CERTIFICATE

94 NOV 22 AM 9:41

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Joanna Spray
CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

For corners in
Cheboygan

(County)

Located In:

Corner Code #

1. Public Land Survey	T	38N	R	2W	L-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James H. Granger, in a field survey on August 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Original Survey Set wood post, 9" Fir N 28°E 8 lks, 9" Fir S 80°E 2 lks.
Harvey Mellen
1927 MSHD
1993 Delmer Porter #15410 Fd Pk nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. Pk nail. Removed Pk nail and Fd 1 1/2" pipe below road. Rewitnessed pipe using 3 witnesses from Porter survey. Added a 4th witness. Reset 5/8" rebar w/aluminum cap in Monument Box.

Marvin A. Russ
Cheboygan County
NOV 21 1994
Re-Monumentation

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" rebar w/aluminum cap in Monument Box

PP	N 42°E	56.00'
10" Maple	N 88°E	36.64'
PP	S 12°E	116.17'
PP	S 28°W	75.29'

LIBER 010 PAGE 49

STATE OF MICHIGAN
JAMES H. GRANGER
PROFESSIONAL SURVEYOR
No. 16041
LICENSED PROFESSIONAL SURVEYOR

Witnessed by James H. Granger
Surveyor's Michigan License No. 16041

Date 11-18-94