

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 2 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 16 - 17

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 3, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

6" W. Birch S 8 W 24.9'

6" W. Birch S 71 W 27.1'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey in this township. Set corner from remains of the probable U. S. BT stumps, but unable to locate a post in very rocky soil. This point conforms very well with corners south for line and distance and is very likely a restoration of the U. S. corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Osting* DATE June 21, 1963
REGISTERED LAND SURVEYOR #10768