

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 2 W.
T. 38 N.R. 3 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 19 - 24

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 22, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" Cedar N 32 W 25.1'

10" Cedar S 82 E 21.7'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between section corners, while making a survey, in this area. Unable to identify U. S. BTs, but this point falls in old N - S grade and near old E - W trail. An old stump, blazed four sides is about 20 feet northwest, but cannot identify it as a U. S. BT.

SURVEYOR'S SEAL

SIGNED *Kenneth Wething* DATE June 25, 1963
REGISTERED LAND SURVEYOR