

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 38 N.R. 2 W.
T. 38 N.R. 3 W.
Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 7 - 18 - 12 - 13

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 2, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" W. Birch S 2 E 41.0'

7" W. Birch N 73 W 49.3'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a retracement survey in this township. Set this corner on line over 1/4 corner and section corner west, making the 1/2 miles between 12 - 13 of equal measurement. Unable to locate anything for a previous corner. Proportionate measurement would place this corner unreasonably east and north of our location, and in no way compatible with occupation or other evidence available at others corners in vicinity. Seems reasonable to assume the 1/4 corner between 12 - 13 was placed somewhere near midpoint, on line between section corners, and we restored this corner with that possibility in mind. Falls about 30 links north of center E - W county road.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostberg* DATE June 13, 1963
REGISTERED LAND SURVEYOR #10068