

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N. R. 2 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19 - 20 - 29 - 30

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 17, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" Cedar S 14 E 22.5'

9" Cedar S 78 W 8.7'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found two very old posts at corner, which probably perpetuate the government post. Both USBT stumps here also, but do not conform very well for bearing and distance. The NW cedar longbutt is down but with good upper face and some marks, but is N 69 W 28 links. A large cedar stump SE. No way to make U. S. record agree exactly, so considered the old posts as best location for corner. Old witnesses face this corner also. Definitely an original government corner.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostberg DATE April 23, 1963
REGISTERED LAND SURVEYOR
#10068