

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 2 W
T. 38 NR 3 W


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to sections 30-31-25-36

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED November 30, 1962

WITNESSES TO CORNER.....



12" Cedar - N45W - 17.6 feet

8" Cedar - S70E - 34.1 feet

AND 4" Cedar - N40E - 16.0 feet

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey in this area. Set corner from NE USBT stump, a Cedar longbutt with upper face and marks. Corner falls in center of old N-S township grade, at old fence line. Found small stake point at corner, when placing monument.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE December 19, 1962
REGISTERED LAND SURVEYOR