

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N. R. 3 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 14 - 23

CORNER MONUMENT Set a" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 21, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" Aspen N 22 W 21.2'

7" Aspen S 72 E 9.2

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line between section corners while making a survey in this area. Falls about 5 feet west and three feet north of old fence corner. U. S. BTs all gone. Checks swamp edges good.

SURVEYOR'S SEAL

SIGNED *Kenneth Ostling* DATE June 24, 1963
REGISTERED LAND SURVEYOR #0068