

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 38 N.R. 3 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 23 - 24

CORNER MONUMENT Corner Monument: Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 21, 1963

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" Cedar S 28 E 17.6'

6" Cedar S 12 E 1.5'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between section corners while making a survey in this area. Many stumps in vicinity but can identify nothing positive. Fits fence line good in S 1/2 of section.

SURVEYOR'S SEAL

SIGNED *Kenneth Osting* DATE June 24, 1963
REGISTERED LAND SURVEYOR #10068