

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 38 N.R. 3 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13 - 14 - 23 - 24

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED May 21, 1963

WITNESSES TO CORNER.....



5" maple S 17 E 16.8'

6" maple N 38 E 17.8'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was set by double proportionate measurement between corners one mile, N - S - E - W, while making a survey in this area. No evidence of a previous corner and U. S. BTs all gone. Checks swamp edges good.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostberg* DATE June 24, 1963  
REGISTERED LAND SURVEYOR #10068