

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 3W


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28, 29, 32, and 33.

CORNER MONUMENT 1" pipe with 1/4" brass cap.

DATE MONUMENT PLACED AND WITNESSED April 25, 1961

WITNESSES TO CORNER..... 5" Maple - S47E 3.1 ft.



7" Maple - S40W 8.7 ft.

8" White Birch - N11E 24.2 Ft.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew. Set corner by proportionate measurement between section corner north and 1/4 corner south at a point 5.00 chains west of original closing corner on west boundary of private claim. Nothing left for government BTs.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE May 22, 1961