

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 39 N.R. 3 W


Cheboygan COUNTY

DESCRIPTION OF CORNER NE corner of Private Claim #334, at lake

CORNER MONUMENT 1" pipe with 4" A luminum cap

DATE MONUMENT PLACED AND WITNESSED 8/30/61

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" Spruce - S39 1/2 W - 74.3 feet

Center of 2'x2' Boulder - S82W - 49.7 feet

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established during a survey of the Private Claim area. Set corner on the true SE'ly boundary of Claim, at the lake shore, on a slight rise above water to protect from ice action and erosion. This corner was set relative to the closing corner between Sections 33-34 on this boundary. No evidence of a previous corner, and original corner probably lost. See map and Minutes of survey of this project for more information.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostberg DATE 9/18/61  
REGISTERED LAND SURVEYOR