

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 NR 19 W

Delta

COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 27-28-33-34
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER

10" Y. Birch	N 54° E	25½ links
	"S 27 NBT"	
7" Hard Maple	S 50° E	26 links
	"S 34 NBT"	
9" Hard Maple	N 65° W	79 links
	"S 28 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set section corner at beech tree with blazes north and south sides.

Found one set of blazes 70 years old and one set 100 years old.

Position fits rock ledge 50 links east. Rock ledge 52 chs. north and rock ledge 32.10 chs. south.

Found several blazes north and south of this position.

Position fits original meander corner 1 mile south.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 8/25/57
REGISTERED LAND SURVEYOR