

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 37 N R 24 W

DESCRIPTION OF CORNER Section corner for sections ^{20/21} 29/28

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6/18/69, F. J. Bray

WITNESSES TO CORNER..... 6" cedar (S 21) (NBT) N 72° E, 05 links



7" cedar (S 20) (NBT) N 84° W, 11 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners one mile to east and to west and 1/4 corners 1/2 mile north and 1 1/2 miles to south. Squared cedar tree near. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 6/26/69
REGISTERED LAND SURVEYOR
Frank J. Bray

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68