

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 37 N R 24 W

DESCRIPTION OF CORNER Section corner for sections $\frac{9}{10}$
 $\frac{16}{15}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6/30/69, F. J. Bray

WITNESSES TO CORNER..... 10" Hemlock (S.15) (NBT) S 38° E, 13 links



10" Hemlock (S.9) (NBT) N 73° W, 15 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by proportioned between section corners one mile to north and to south. 1/4 corner 1/2 mile west and stream which checks fairly well to the east. No original evidence found. Blazes on stump and trees in vicinity.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE 7/16/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68