

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.'s $\frac{38}{37}$ N.R. 24W


Delta COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{35}{36}$ T38N, R24W
2/1 T37N, R24W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9/24/68, F. J. Bray

WITNESSES TO CORNER..... 10" Cedar (S.36) (NBT) N 52° E, 10 links



11" Cedar (S. 2) (NBT) S 54° W, 15½ links

Old scribed post S 60° E, 18½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from 2 original tamarack B.T.'s. B.T. to SE has scribe marks on upper face and overgrowth of scribe marks and notch on lower face. Found overgrowth of scribe marks of upper face and of notch on B.T. to SW. Both down and chopped on.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 12/4/68
REGISTERED LAND SURVEYOR

Frank J. Bray