

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37. NR. 24 W.

Delta COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19-20-29-30. . . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	8" Cedar	N 77° W "S 19 NBT"	28½ links
	6" Cedar	N 14° E "S 20 NBT"	26 links
	7" Cedar	S 79° E "S 29 NBT"	48 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from one W. Pine B.T. bearing S 66° E 41 links.
Stump remains with notch and part of witness blaze.

Corner lies in swamp.

Corner found by C. Limpert, District Forester in 1947 while cruising timber.

Location poster placed 4 chs. south on winter road.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/13/57
REGISTERED LAND SURVEYOR