

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37. NR. 24 W.

Delta COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 7-8

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 5" Hard Maple S 81° W 30 links
"1/4S NBT"

5" Hard Maple N 32° W 48 1/2 links
"1/4S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner as set by Marcus McNabb, County Surveyor, in 1924.

Found old cedar stake in place. Checked site of beech tree marked by McNabb as new witness. Tree gone but turnout remains. Checked distance 5.00 chs. north to swamp edge.

1/4 Corner lies on NW corner of cleared field and 1/2 chs. north of road.

1/4 Corner found by C. Limpert, District Forester.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 2/13/57
REGISTERED LAND SURVEYOR