

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37.. NR. ~~24~~25.. W

D e l t a - M e n o m i n e e COUNTY

DESCRIPTION OF CORNER ~~Section corner common to Sections 7, 18, 12, 13~~ ..

DESCRIPTION OF CORNER MONUMENT .. 1" Pipe with 4" Brass Cap ..

WITNESSES TO CORNER 11" Soft Maple (S 7 NBT) .. N 24° E 46 Links ..

12" Hemlock .. (S 13 NBT) .. S 5° W 35 Links ..

12" Hemlock .. (S 7 NBT) .. N 70° E 35 Links ..

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced at old scribed wood post set by unknown surveyor Found a Cedar Stump bearing S 39° W 37 Links. This is not an original but is marked "B.T." Found down and rotted Cedar S 26° E 33 Links (Possible B. T.) Distance east 9.00 chains and west 2.00 chains to swamp edges check with record distance.

Corner was placed and witnessed August 26, 1960 with C. Limpert, D. F.
and J. Bastian.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 9/14/60
REGISTERED LAND SURVEYOR
Billy D. Buckler