

✓  
MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 37 N.R.'s 24 and 25 W


Delta and Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections  $\frac{13}{18}$   $\frac{24}{19}$

CORNER MONUMENT 1" iron pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 5/23/68, F. J. Bray

WITNESSES TO CORNER..... 9" Tamarack (S.13) (NBT) N 50° W, 05 links



8" Cedar (S.19) (NBT) S 10° E, 19 links

AND

CIRCLE CORNER REGISTERED

### DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished placing on line and the single proportioned measurement between section corners one mile to north and one mile to south. Blazed trees near. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/10/68  
REGISTERED LAND SURVEYOR  
Frank J. Bray